Bruhat Bangalore Mahanagara Palike
Excecutive Engineer Yelahanka Project Division

Name of Work: (Package -5)

Sl No.	Description	Estimate Cost, Lakhs
1	Improvements of Road Adjacent to Yelahanka Lake from Kenchenahalli to Chowdeshwari Temple in Ward No. 02	300.00
2	Improvements and Asphalting to New Post Office main road and cross roads in Ward No. 01	35.00
3	Improvements and Asphalting to Sugappa layout cross roads in Ward No. 01	40.00
4	Improvements and Asphalting to Shanimahathma swamy temple road and Surabhi layout 2nd main and cross roads in Ward No. 01	40.00
5	Asphalting to Balance Roads in A & B Sector of Yelahanka New Town in Ward No. 04	50.00
	Total Cost of the Project, Lakh Rs	465.00

Abstract Bill of Quantities

Sl No	Description of Item	Unit	Total Quantity	Rate, Rs	Amount, Rs
1	Removing B.S.Slabsand stacking etc complete.	Sqm	2591.50	65.72	170313.38
2	Refixing stone slabs of drains and pointing in C.M (1:3).	Sqm	2372.65	80.56	191140.68
3	KSRRB 200-9. Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of thorney jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials labour charges complete as per specifications. MORTH / Chapter 2	Sqm	13056.00	9.54	124554.24
4	KSRRB 200-1. Cutting of trees girth from 300mm to 600mm including cutting of trunks, branches and removal of stumps stacking of serviceable materials earth filling in the depressions / pit, labour charges complete as per specifications. MORTH specification clause 201/ Chapter 2	Each	25.00	200.34	5008.50
5	Removing stumps, tree roots, roots of bamboo cluster etc., with 8.2.2 girth above 1.50 m and upto 3.00 m including excavation, stacking materials neatly and levelling area etc., complete with lead upto 50 m and all lifts.	Each	25.00	88.00	2200.00
6	Dismantling Mangalore tiles roof and stacking the material within a radius of 50 meters. - - A.C. sheet roofing.	Sqm	596.17	65.72	39180.23

Administrative Approval
Accorded For ..465.24 Lakhs
Head of A/C....P-3158 (SIP)
CER NO :..192/17-18 Dt:.. 16/03/18
S.E. (Project)
7.16/3

Technical Sanction
Accorded For ...465.24 Lakhs
Head of A/C....P-3158 (SIP)
CER NO :...171/17-18 Dt:.. 1-08-17
[TA] CE (YNK)

Scanned by TapScanner